BRUHATH BANGALORE MAHANAGARA PALIKE,
Office of the Executive Engineer Dasarahalli Division,
Schedule-B

NAME OF WORK: Road and Footpath maintenance in ward no.15 Dasarahalli

Sl. No	Description of work	Unit	Qty	Rate quoted by the Contractor T.V.Gangappa	
				In Figures (Rs.)	Amount
1	2	3	4	5	7
1	Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications	Cum	72	250.0	18000
2	Supplying fixing precast reinforement concrete slabs 10cm thick including cost of reinforecemet as per design and drawing material cost transpotation hire charges of machinery. Machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges labour charges of cost of all materials.	Sqm	250.2	1075.0	268965

T.V. Gangappa
Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer
Dasarahalli Division
BBMP

Signature of the Contractor